


15-145-20782-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Pawnee County, Sec. 10 Twp. 22S Rge. 15 NE/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
SE SW SE
Lease Owner Carstan Oil Co., Inc.
Lease Name Rollo Well No. 1
Office Address 8600 W. 63rd - Suite 307, Shawnee Mission, Ks.
Character of Well (Completed as Oil, Gas or Dry Hole) 66202
Dry Hole
Date Well completed 1-16 19 81
Application for plugging filed 1-16 19 81
Application for plugging approved 1-16 19 81
Plugging commenced 1-16 19 81
Plugging completed 1-16 19 81
Reason for abandonment of well or producing formation



Locate well correctly on above
Section Plot

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Marion Smith
Producing formation Depth to top Bottom Total Depth of Well 4002'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	284'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from feet to
feet for each plug set.

- 600' - 70 sx cement
- 270' - 25 sx cement
- 40' - 10 sx cement
- 3 sx cement in rathole
- 2 sx cement in water well

RECEIVED
JAN 30 1981
1-30-81
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor White & Ellis Drilling, Inc.
401 E. Douglas-Suite 500 Wichita, Kansas 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.
Ernest Sifford (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
is filed and that the same are true and correct. So help me God.

(Signature) Ernest Sifford
401 E. Douglas-Suite, 500 Wichita, Kansas
(Address) 67202

SUBSCRIBED AND SWORN TO before me this 29th day of January, 1981

CAROLYN J. TJADEN
NOTARY PUBLIC
STATE OF KANSAS
My Appt. Expires Sept. 5, 1984

Carolyn J. Tjaden
Carolyn J. Tjaden - Notary Public.

My commission expires

DRILLERS LOG

15-145-20782-0000

OPERATOR: CARSTAN OIL CO., INC., 860 West 63rd - Suite 307, Shawnee Mission, Ks. 662

CONTRACTOR: White & Ellis Drilling, Inc., Box 448, El Dorado, Kansas 67042

Lease Name Rollo Well No. 1

Sec. 10 T. 22S R. 15W Spot SE SW SE

County Pawnee State Kansas Elevation _____

Casing Record:

Surface: 8 5/8" @ 284' with 200 Sxs. 3% CC - 2% Gel

Production: _____ @ _____ with _____ Sxs.

Type Well: -D & A Total Depth 4002'

Drilling Commenced: 1-10-81 Drilling Completed 1-16-81

Formation	From	To	Tops
Cellar	0	5	Mississippi 3560
Sand	5	70	Simpson 3940
Sandy Shale	70	130	
Sand, Shale	130	289	
Shale	289	400	
Sand	400	488	
Shale	488	813	
Shale, Sand	813	1490	
Shale, Lime	1490	3560	
Lime	3560	3872	
Lime, Shale	3872	3940	
Sand	3940	3955	
Lime, Shale	3955	4002	

STATE OF KANSAS
 JAN 30 1981
 CONSERVATION DIVISION
 Wichita, Kansas

COMPLETION RECORD

Liner Record: Size _____ From _____ To _____

Cementing Record: _____ Sacks _____

Perforating Record:

Formation	Perforated Interval	Number Shots

Initial Production: _____

Electric Log	Type and Depths Covered