

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Pawnee County, Sec. 24 Twp. 22 Rge. 16 ~~XXX~~ (W)

Location as "NE/CNW/SW" or footage from lines SW SW NW

Lease Owner D.R. Lauck Oil Company, Inc.

Lease Name Rice Well No. 1

Office Address 301 South Broadway Wichita 2 Kans

Character of Well (completed as Oil, Gas or Dry Hole) gas

Date well completed Oct. 8- 19 56

Application for plugging filed Octy Dec. 3 19 56

Application for plugging approved Dec. 7 19 56

Plugging commenced Dec. 10 19 56


Plugging completed Dec. 14 19 56

Reason for abandonment of well or producing formation _____

high water content- low gas output

If a producing well is abandoned, date of last production no 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Mr. Brundage

Producing formation Arbuckle Depth to top 4016 Bottom 4062 Total Depth of Well 4062 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Arbuckle	gas & water	4016	4062	8 5/8 5 1/2	220 4062	none 3492

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Squeeze perf 4014 to 4025 w/25 sx cement;
dumped 5 sx cement to 3990
surface hole squeezed & w/30 sx mud and 80 sx cement;
to top of surface pipe

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor R & S Pipe Pulling Co.

Address Ellinwood Kans

STATE OF Kansas, COUNTY OF Sedgwick, ss.

John H. Knightley (employee of owner) ~~or (owner or operator)~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John H. Knightley
Wichita Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 20 day of December, 19 56

My commission expires Sept. 14, 1959

Elizabeth Gay
Notary Public.

RECEIVED
STATE CORPORATION COMMISSION

DEC 21 1956 12-21-56

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC. 24 T. 22 R. 16w
BOOK PAGE 123 LINE 16

D. R. Lauck Oil Company, Inc.
and Sunray Mid-Continent Oil Company

Rice No. 1

SW SW NW 24-22S-16W
Pawnee County Kans.

Commenced: September 17, 1956

Completed: September 29, 1956

Casing Record: 220' 8 5/8" cem. w/200 sx
4062' 5 1/2" cem. w/75 sx

Elevation: GR 1999; DF 2001; KB 2003

Drillers Log

			Tops	
surface clay	20	Heebner	3450-1447	3450-1447
sand	120	Toronto	3468-1465	3468-1465
shale	220	Brown Lime	3562-1559	3562-1559
blue shale	315	Lansing	3570-1567	3570-1567
Dakota sand	340	Base Kansas City	3816-1813	3814-1811
red bed	975	Mississippian (?)	3904-1901	3904-1901
shale & shells	1500	Kinderhook (?)	3916-1913	3916-1913
shale & salt	1750	Viola	3944-1941	3946-1943
Anhydrite & shale	1800	Simpson Shale	3973-1970	3973-1970
shale & shells	1900	Arbuckle	4016-2013	4016-2013
lime & shale	1985	Rotary Total Dep	4062-2059	4060-2057
lime	2375			
shale & lime	2785	DST #1 (M-D) 4017-4025	open 1 hr; gas	
shale & shells	2947		to surface 2 min; gas gauged	
shale & lime	3185		2,130,000 CFG; Recov. 150' black	
broken lime & shale	3290		gas cut mud with trace water;	
lime & shale	3680		IFP 530#, FFP 530# BHP 1280#	
lime	3910		in 30 min.	
lime & chert	3960	DST #2 (W) 4025-4035	open 40 min;	
lime	4000		gas to surface 1 minute, gauged	
lime & shale	4016		1,450,000 CFG; hold full fluid	
lime	4062		and flowed into pits in 17 min;	
rotary total depth	4062		shut in 30 min. recov. 135' clear	
			gassy oil, 455' water,	
			IFP 490#, FFP 780#, BHP 1280#.	

RECEIVED
STATE CORP. REG. DIVISION
DEC 7 - 1956
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING

FILE SEC. 24 T. 22 R. 16 W
BOOK PAGE 123 LINE 16