


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

Pawnee County, Sec. 26 Twp. 23S Rge. (E) 15 (W)  
Location as "NE/CNW%SW%" or footage from lines SE SW SE  
Lease Owner Natural Gas and Oil Company  
Lease Name Walker Well No. 1  
Office Address Box 105, Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) oil well  
Date well completed April 25 19 56  
Application for plugging filed July 28 19 56  
Application for plugging approved July 30 19 56  
Plugging commenced August 5 19 56  
Plugging completed August 12 19 56  
Reason for abandonment of well or producing formation Production depleted,  
uneconomical to operate due to excessive water hauling.  
If a producing well is abandoned, date of last production July 15 1956  
Was permission obtained from the Conservation Division or its agents before plugging was com-  
menced? yes



Locate well correctly on above  
Section Plat

Name of Conservation Agent who supervised plugging of this well R. M. Brundage  
Producing formation Arbuckle Depth to top 4130 Bottom 4133 Total Depth of Well 4135 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface		-0-	220'	8 5/8"	220	None
				5 1/2"	4130	3291'9"

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugged back with sand to 4150'. Dumped 5 sacks of cement with dump bailer. Pumped 20 sacks of mud and 5 sacks of hulls down pipe to spot oil. Squeezed surface pipe (Globe Cementing Co.), using 15 sacks of mud followed by 3 sacks of calcium chloride and 80 sacks of cement. Checked top of cement 8' from surface. Dumped cement from 8' to top of surface.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor E & L Casing Pulling Co.  
Address Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.  
J. B. STEELE, JR. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. B. Steele, Jr.  
Box 105, Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 27th day of August, 19 56

My commission expires July 27, 1959

cc: State Corporation Commission  
New Orleans - 2  
Wichita  
File

**RECEIVED**  
STATE CORPORATION COMMISSION  
AUG 28 1956  
CONSERVATION DIVISION  
Wichita, Kansas  
Notary Public.

**PLUGGING**  
FILE SEC 26 T 23 R 15 W  
BOOK PAGE 84 LINE 37

8-28-56

DRIILLING LOG

Company: Natural Gas & Oil Company

SE 1/4 SE

Farm Name: Walker

Well No. 1

Sec. 26, Twp. 23S, Rge. 19E,

Total Depth: 4135'

County: Pawnee, Kansas

Comm: 4/14/56 Comp: 4/25/56  
Contractor: Paul Brothers, Inc.

Elevation:

Casing: 3 5/8" 230' con.  
5 1/2" 4135' con.

Production:

Figures below indicate bottoms of formations:

Sand, gravel and shale	0 -	232
Redbed		420
Sand		470
Redbed and sand streaks		993
Anhydrite		992
Shale and shells		2150
Redbed, shale and shells		2755
Lime and shale		3055
Lime		3975
Lime and shale		4005
Viola		4095
Simpson		4120
Arbuscula		4135
Total Depth		4135

This is to certify that the above information is to the best of our knowledge, true and correct.

PAUL BROTHERS, INC.

By: Al. H. Smith

SUBSCRIBED AND SWORN TO before me this 1st day of May, 1956.

My commission expires: Jan. 11 - 1959

Sequid R. Lewis  
Notary Public

PLUGGING  
FILE SEC. 26 T 23 R 15W  
BOOK PAGE 84 LINE 37