


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Pawnee County, Sec. 26 Twp. 25S Rge. 15 (E) W (W)

Location as "NE/CNW/SW" or footage from lines SE SE SW  
Lease Owner Natural Gas & Oil Company  
Lease Name Blount Well No. 1  
Office Address Route 1, Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed May 10, 1956  
Application for plugging filed May 10, 1956  
Application for plugging approved May 10, 1956  
Plugging commenced May 10, 1956  
Plugging completed May 10, 1956  
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well R. M. Brundage  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4190 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	243	8 5/8"	243	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

From 4190' to 241 1/2' - heavy rotary mud  
241 1/2' to 240' - wooden plug  
240' to 178' - 20 sacks cement  
178' to 41 1/2' - heavy rotary mud  
41 1/2' to 40' - wooden plug  
40' to 6' - 10 sacks cement  
6' to surface- cellar

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Peel Brothers, Inc.  
Address P.O. Box 88, Hoisington, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.  
Peel Brothers, Inc. (employee of owner) or (~~owner~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. PEEL BROTHERS, INC.

(Signature) BY: Al H. Smith  
P.O. BOX 88, Hoisington, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of May, 19 56

My commission expires April 27, 1960 Notary Public.

PLUGGING  
FILE SEC. 26 T. 23 R. 15W  
BOOK PAGE 60 LINE 30

RECEIVED  
STATE CORPORATION COMMISSION  
Notary Public.

5-19-56

DRILLERS' LOG

Company: Natural Gas & Oil Company

SE. SE. SW  
Sec. 26, Twp. 25S, Rge. 15W

Farm Name: Blount Well No. 1

County: Pawnee,  
Kansas

Total Depth: 4190' RS

Comm: 4/27/56 Comp: 5/10/56

Contractor: Peol Brothers, Inc.

Elevation:

Casing: 8 5/8" 243' cem.

Production: Dry

Figures below indicate bottoms of formations:

Sand	0 -	100
Shale and red bed		200
Red bed		400
Sand		460
Red bed and sand		940
Anhydrite		960
Red bed		1245
Shale		1925
Lime and shale		2090
Shale and shells		2400
Shale and lime		3589
Lime		3738
Lime and shale		3792
Lime		4032
Shale and lime		4071
Viola		4097
Lime		4190
Total Depth		4190

This is to certify that the above information is to the best of our knowledge, true and correct.

PEOL BROTHERS, INC.

BY: Al. H. Smith

SUBSCRIBER AND SWORN to before me this 15th day of May, 1956.

My commission expires: April 27, 1960

Ruth Beck  
Notary Public

PLUGGING  
FILE SEC-26 T-23 R15W  
BOOK PAGE 60 LINE 30