

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-145-21,192-0000

LEASE NAME Ratzlaff

WELL NUMBER 1-26

330 Ft. from S Section Line

3630 Ft. from E Section Line

SEC. 26 TWP. 22S RGE. 15 (E) or (W)

COUNTY Pawnee

Date Well Completed 3/28/85

Plugging Commenced 3/28/85

Plugging Completed 3/28/85

LEASE OPERATOR HOLD OIL CORP.

ADDRESS 7136 S. Yale, Ste. 208, Tulsa, OK 74136

PHONE#(918) 492-8524 OPERATORS LICENSE NO. 4230

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? S.W. Dist. #1, Steve Durrant

Is ACO-1 filed? attached If not, is well log attached? yes

Producing Formation None Depth to Top N/A Bottom N/A T.D. 4060'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
See Attached				8 5/8"	305'	-0-
ACO-1						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Hole loaded w/ DM, cmtd 200' plug from 930'-730' w/ 50 sx 60/40 poz mix, cmtd 160' plug from 330' - 170' w/ 40 sx 60/40 poz mix, cmtd. 40' plug from 40' - surface w/ 10 sx 60/40 poz mix, wooden plug 40', sfc pipe cut 3' below GL, well P&A

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Glacier Drilling Co., Inc. License # 5825

Address 825 Commercial Street, Emporia, Kansas 66801 STATE CORPORATION COMMISSION

STATE OF Kansas COUNTY OF Lyon, ss. APR 29 1985 4-29-85

Gregory Lanham, Production Coordinator (Employee of Operator) of above-described well, being first duly sworn on oath, says: That I have known the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Gregory Lanham

(Address) 7136 South Yale, Ste. 208 Tulsa, OK 74136

SUBSCRIBED AND SWORN TO before me this 24th day of April, 1985

Herri D. Jones Notary Public

My Commission Expires: Oct. 27, 1987