

STATE OF KANSAS
STATE CORPORATION COMMISSION


Give All Information Completely
Make Required A...
Mail or Deliver Re...
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

STAFFORD County. Sec. 32 Twp. 22s Rge. 13 (X) (W)

Location as "NE/CNW&SW" or footage from lines NW NW NE
Lease Owner: PETROLEUM, INC.
Lease Name: MILTON "B" Well No. 1
Office Address: ROUTE #2, GREAT BEND, KANSAS
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE
Date well completed: AUGUST 9 19 65
Application for plugging filed: AUGUST 9 19 65
Application for plugging approved: AUGUST 9 19 65
Plugging commenced: AUGUST 9 19 65
Plugging completed: AUGUST 9 19 65
Reason for abandonment of well or producing formation NO PRODUCIBLE ZONE

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production NONE 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well ARCHIE ELVING
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3900 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	320'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

MUDDED UP WITH HEAVY MUD TO 220', FOLLOWED BY WOODEN PLUG, PLACED 1/2 SACK HULLS AND 25 SACKS CEMENT THROUGH DRILL PIPE ON TOP OF PLUG. MUDDED UP WITH HEAVY MUD TO 40' FOLLOWED BY WOODEN PLUG, PLACED 1/2 SACK HULLS AND 10 SACKS CEMENT ON TOP OF PLUG TO BASE OF WELL CELLAR.

RECEIVED
STATE CORPORATION COMMISSION

AUG 18 1965

CONSERVATION DIVISION
Wichita, Kansas

8-18-65

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor: GARVEY DRILG. Co.
Address: R.R. #2, GREAT BEND, KANSAS

STATE OF KANSAS, COUNTY OF BARTON, ss.
MONTE CHADD (employee of owner) or (owner/owner's representative) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. MONTE CHADD, DIST. PROD. SUPT.

(Signature) *Monte Chadd*
ROUTE #2, GREAT BEND, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 17 day of AUGUST, 19 65

My commission expires MAY 28, 1969

Richard H. Dumber
Notary Public.

WELL LOG

15-185-00494-0001

COMPANY Petroleum, Inc.

SEC. 32 T. 22S R. 13W

FARM Milton (Washdown) NO. 1

LOC. NW NW NE

TOTAL DEPTH 3900'

COUNTY Stafford

COMM. 8-6-65

COMP. 8-8-65

CONTRACTOR Garvey Drilling Company

CASING 8 5/8" @ 320' w/200 sx

ELEVATION 1920' KB

PRODUCTION D & A

FIGURES INDICATE BOTTOM OF FORMATIONS

This test is a washdown of the old Palmer, #1 Milton drilled in 1950.

Garvey Drilling Company started washing on August 6, 1965, washed to old TD 3887', and drilled to a new TD 3900'.

3900' Arbuckle

RECEIVED
STATE CORPORATION COMMISSION

AUG 18 1965

CONSERVATION DIVISION
Wichita, Kansas

State of Kansas

County of Barton

SS

I, Sam N. Stephens of Garvey Drilling Company

upon oath state the above and foregoing is a true and correct copy of the log of the #1 Milton (Washdown) well.

Sam N. Stephens

Subscribed and sworn to before me this 17th day of August 1965

My Commission Expires: May 28, 1969

Richard H. Dumbler
NOTARY PUBLIC