

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

WELL PLUGGING RECORD

Stafford County, Sec. 32 Twp. 22 Rge. 13 (E) W (W)

Location as "NE/CNW/SW" or footage from lines SW SW SE

Lease Owner Lee Phillips Oil Company

Lease Name Metz Well No. 1

Office Address Union Nat'l Bk Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 8-1 19 52

Application for plugging filed 8-1 19 52

Application for plugging approved 8-1 19 52

Plugging commenced 8-1 19 52

Plugging completed 8-1 19 52

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough

Producing formation Depth to top Bottom Total Depth of Well 3940 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	330	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Top plug set at 35' with 10 sacks cement
Bottom plug set at 300' with 20 sacks cement

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Anschutz Drilling Company, Inc.
Address 709 Union Nat'l Bk Bldg., Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Leon L. Mehler (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leon L. Mehler
709 Union Nat'l Bk Bldg., Wichita, Ks.
(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of August, 19 52

My commission expires May 2, 1956

24-2675-5 2-52-20M

PLUGGING
FILE SEC 32 T 22 R 13
BOOK PAGE 35 LINE 7

RECEIVED
STATE CORPORATION COMMISSION
AUG - 8 1952
CONSERVATION DIVISION
Wichita, Kansas

DRILLER'S LOG

Lee Phillips Oil Company
 #1 Metz
 SW SW SE - 32-22S-13W
 Stafford County, Kansas

FROM	TO		
0	285	Sand	COMMENCED: 7-20-52
285	595	Red Bed & shale	COMPLETED: 8-1-52
595	800	Red rock	
800	835	Anhydrite	CASING RECORD
835	1055	Shale, red rock & shells	Set 8-5/8" surface casing at 330
1055	1200	Shale & shells	feet with 200 sacks cement
1200	1380	Salt, shale & shells	and 2 sacks calcium chloride.
1380	1630	Shale & shells	
1630	1680	Shale & lime	
1680	1825	Lime	
1825	1905	Sandy lime & shale	
1905	2160	Lime	
2160	2430	Shale & lime	
2430	2575	Broken lime & shale streaks	
2575	2730	Shale, lime & shells	
2730	2905	Shale & lime	
2905	2955	Lime	
2955	3045	Shale & lime	
3045	3115	Lime	
3115	3210	Lime, broken	
3210	3285	Lime & shale	
3285	3400	Lime	
3400	3415	Shale	
3415	3490	Shale & lime	
3490	3804	Lime	
3804	3849	Viola chert	
3849	3875	Simpson shale	
3875	3905	Shale	
3905	3925	Arbuckle	
3925	3940	Lime Arbuckle	
	3940	TOTAL DEPTH	
		D&A	

STATE OF KANSAS

COUNTY OF SEDGWICK

I hereby affirm that the foregoing is a true and correct copy of the log of Lee Phillips Oil Company's #1 Metz, located SW SW SE of Section 32-22S-13W, Stafford County, Kansas.

ANSCHUTZ DRILLING COMPANY, INC.

BY:

Leon L. Mehler
 Leon L. Mehler

Subscribed and sworn to before me this 6th day of August, 1952.

Jacqueline L. Kansas
 Notary Public

My commission expires: May 2, 1956.

