

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

MAY 20 1974

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Little Gearge Oil Company

Complete Address 225 Sutton Place, Wichita, Kansas 67202

Lease Name Doll Well No. A-1

Location NW NW SW Sec. 25 Twp. 22 Rge. (E) (W) 16

County Pawnee Total Depth 4055'

Abandoned Oil Well        Gas Well X Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor F & F Well Service

Address Towanda, Kansas 67144 License No. 714

Operation Completed: Hour 9:30 A Day 15 Month 5 Year 1974

The above well was plugged as follows:

Total Depth 4055' 8 5/8 csg set at 271' cwc 225 sk.

4 1/2 csg set at 4054 cw 100 sk cem. With top perf. (3970-3997)

Pumped 45 sk cem plug top of cement 3600'.

Shotoff and recovered 2020' of 4 1/2 csg.

Pumped down 8 5/8 csg with 20 sk gel & water W/300 lbs hulls, -released 8 5/8 plug

and pumped 100 sk comm cement by Sun Cementing Co. PP 300 lbs.

I hereby certify that the above well was plugged as herein stated.

Signed: Geo F. Massey  
Well Plugging Supervisor

INVOICED

DATE 5/21/74

INV. NO. 9149-W