

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
SEP 15 1971
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Louis M. Mai

Complete Address Box 33, Russell, Kansas 67665

Lease Name Crawford "A" Well No. # 13

Location SW NE SW Sec. 2 Twp. 14 Rge. 15 (E) (W) W

County Russell Total Depth 3304

Abandoned Oil Well Gas Well Input Well SWD Well X D & A

Other well as hereafter indicated

Plugging Contractor Southwest Casing Pulling Company

Address Box 364, Great Bend, Kansas License No. # 399

Operation Completed: Hour 4 P.M. Day 10 Month 9 Year 1971

The above well was plugged as follows:

12 1/2" csg. 925'.
Sanded hole back to 3275' & displaced 6 sax cement with dump bailer. No pipe re-
covery. Set plug @ 900'. Squeezed 7" csg. with 35 sax mud, 7 sax hulls, 85 sax
cement, 15 sax mud, 3 sax hulls, & 15 sax cement. Squeezed 12 1/2" csg. with 100
sax cement with Halliburton Cementing Company's pump truck, cementing to base of
cellar. Displaced 6 yds Ready-mix Cement outside 12 1/2" csg. cementing to base
of cellar. Cement traveled down hole 250' inside csg., displaced 8 yds. Ready-mix
Cement, cementing from 250' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 9-15-71

INV. NO. 4330-W