

R

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

DEC 23 1975

CONSERVATION DIVISION
Wichita, Kansas

12-23-75

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name K-W, Voyager Petroleum Inc. & Sterling Drilling Co.
 Complete Address P. O. Box 129, Sterling, Kansas 67579
 Lease Name Ewing Well No. 1
 Location NE NE NE Sec. 19 Twp. 22 Rge. (E) (W) 16
 County Pawnee Total Depth 4105'
 Abandoned Oil Well Gas Well XX Input Well SWD Well D & A
 Other well as hereafter indicated
 Plugging Contractor Kelso Pipe Pulling
 Address Box 176, Chase, Kansas 67524 License No. 683
 Operation Completed: Hour 11:15 A Day 20 Month 12 Year 1975

The above well was plugged as follows:

Total Depth 4105' 8 5/8 csg set 1030' cwc 550 sk.
4 1/2 csg set 4104' cw 150 sk cem.
4 1/2 csg FBTD 4074' & perf. (4022')
Squeezed 4 1/2 csg with 100 lbs hulls & 35 sk cem. Top of cem. 3700'.
Cutoff & recovered 3160'.
Squeezed 8 5/8 csg with 25 sk gel & water W/100 lbs hulls -released plug & pumped
125 sk 60/40 poz cem. PP 800 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo Massey
Well Plugging Supervisor

DATE 12-26-75

INV. NO. 2460-W