

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

MAR 18 1963

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Frank J. Black

Complete Address: Box 150 Mc Pherson, Kansas

Lease Name Schultz Well No. 1

Location SE SE SE Sec. 14 Twp. 22 Rge. (E) (W) 16

County Pawnee Total Depth 4066

Abandoned Oil Well      Gas Well X Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Knight Casing Pulling

Address: Chase, Kansas License No. 436

Operation Completed: Hour 6PM Day 14 Month 3 Year 63

The Above well was plugged as follows:

8 5/8" 253' circulated with cement - 5 1/2" 4062' with 100 sax cement.

Filled with sand to 4050', set 4 sax cement with dump bailer - pulled 3250' 5 1/2" to 2000' pumped 11 sax mud to kill flow - pulled pipe to 450' circulated hole with heavy mud through 5 1/2" - 14 more sax gel - displaced 25 sax cement through 5 1/2" at 450', heavy mud to 250', displaced 25 sax cement through 5 1/2" - heavy mud to 40', set bridge and cement to bottom cellar.

Mudding and cementing by Knight Company pump truck.

I hereby certify that the above well was plugged as herein stated.

DATE 3/18/63

Signed: [Signature]  
Well Plugging Supervisor

INV. NO. 6932-W

INVOICED