

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

AUG 12 1965

CONSERVATION DIVISION
Wichita, Kansas

8-12-65

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. A. G. Radke of Garvey Drilling Company has this
date requested permission to plug the following described well:

Mr. Radke guarantees payment of the plugging fee.

Operator's full Name: Petroleum Inc.

Complete Address: 352 N. Broadway, Wichita, Kansas

Lease Name: Milton "B" Well No. # 1

Location: NW NW NE Sec. 32 Twp. 22 Rge. 13 (E) (W) W

County Stafford Total Depth 3900' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Radke was instructed to plug the well as follows:

220' of 8 5/8" surface pipe, cement circulated. Fill hole with
drilling mud to 220', 1st cementing plug, bridge with hulls, and
cement with 25 sacks. Fill hole with drilling mud to 40', 2nd
cementing plug, bridge with hulls, and cement with 10 sacks to
base cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving