

State of Kansas



15-185-60001-0000

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Norman Thompson of Garvey Drilling Company has this date requested permission to plug the following described well:

Mr. Thompson guarantees payment of the plugging fee.

Operator's full Name: Petroleum, Inc.

Complete Address: 300 West Douglas, Wichita, Kansas

Lease Name: Ukens "G" Well No. # 1

Location: SE NE NW Sec. 24 Twp. 22 Rge. 13 (E)(W) W

County Stafford Total Depth 3775' Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Thompson was instructed to plug the well as follows:

285' of 8 5/8" surface pipe, cemented with 500 sacks. Fill hole with drilling mud to 250', 1st cementing plug, bridge with 1/2 sack of hulls and cement with 25 sacks. Fill hole with drilling mud to 40', 2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10 sacks to base of the cellar. Bridge and cement rat hole with 2 sacks.

RECEIVED  
STATE CORPORATION COMMISSION

Very truly yours,

MAR 31 1967

Archie Elving  
Conservation Division Agent

CONSERVATION DIVISION  
Wichita, Kansas