



ROBERT B. DOCKING Governor
 WILLIAM L. MITCHELL Chairman
 JAMES O. GREENLEAF Commissioner
 DALE E. SAFFELS Commissioner
 RAYMOND B. HARVEY Secretary
 E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 OCT 29 1968
 CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Bill Banks of Ben C. W. Hyde, Jr. has this date requested permission to plug the following described well:

Mr. Banks guarantees payment of the plugging fee.

Operator's full Name: Ben C. W. Hyde, Jr.

Complete Address: 4000 Somerset Drive, Prairie Village, Mo.

Lease Name: Dair Well No. 1

Location: New Monte Sec. 4 Twp. 22S Rge. 11 (E)(W)

County: Stafford Total Depth 3958 Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Banks was instructed to plug the well as follows:

249' of 8 5/8" surface pipe circulated with cement -
plug - 600' - pumped 50 sacks cement -
mud to 240' - plug - 25 sacks cement -
mud to 40' - 1/2 sack hulls - plug - 10
sacks cement to surface - budge rat hole - 2
sacks cement.

Very truly yours,

R. L. Hansen
 Conservation Division Agent