

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

APR 8 1963

CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Kelso of Knight Casing Pulling has this

date requested permission to plug the following described well:

Mr. Kelso guarantees payment of the plugging fee.

Operator's full Name: Inger Oil Co.

Complete Address: 1020 Central Bldg., Wichita, Kansas

Lease Name: Durham Well No. # 1

Location: NW SW NE Sec. 33 Twp. 22 Rge. 13 (E) (W) W

County Stafford Total Depth 3647 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Kelso was instructed to plug the well as follows:

285' of 8 5/8" surface pipe cement circulated. 3647' of
5 1/2" long string cemented with 100 sacks. Top perforation
3531', squeezed at 2500', plug at 3450'. Fill hole with
mud to 200', 10' rock bridge, cement with 20 sacks.
Fill hole to 40' with mud, 10' rock bridge, cement with
10 sacks to base cellar.

Very truly yours,

Audie Elving
 Conservation Division Agent