

State of Kansas



JOHN ANDERSON, Jr. Governor
 WILLIAM L. MITCHELL, Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

AUG 12 1965

CONSERVATION DIVISION
 Wichita, Kansas

8-12-65

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Donald T. Ingling of Donald T. Ingling has this

date requested permission to plug the following described well:

Mr. Ingling guarantees payment of the plugging fee.

Operator's full Name: Donald T. Ingling

Complete Address: 615 1st National Bank Bldg., Wichita, Ks.

Lease Name: Hallman Well No. # 1

Location: NW NW NW Sec. 36 Twp. 22 Rge. 13 (E) (W) W

County Stafford Total Depth 2890' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Ingling was instructed to plug the well as follows:

287' of 8 5/8" surface pipe, cement circulated with 250 Sacks.
Fill hole with drilling mud to 260', 1st cementing plug, bridge
with hulls, and cement with 25 sacks. Fill hole with drilling
mud to 40', 2nd cementing plug, bridge with hulls, and cement
with 10 sacks to base cellar. Bridge and cement rat hole with
2 sacks.

Very truly yours,

Archie Elving