


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Stafford County, Sec. 35 Twp. 22 S Rge. 14 W (E) (W)  
Location as "NE/CNW/SW" or footage from lines SE SW NE  
Lease Owner ALPINE OIL & ROYALTY CO., INC. et al  
Lease Name WRIGHT Well No. 1  
Office Address 800 Biting Building, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) oil well  
Date well completed February 2, 1964 19  
Application for plugging filed November 9, 1965 19  
Application for plugging approved November 10, 1965 19  
Plugging commenced November 11, 1965 19  
Plugging completed November 16, 1965 19  
Reason for abandonment of well or producing formation non-productive in commercial quantities  
If a producing well is abandoned, date of last production November 9, 1965 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Archie Elving  
Producing formation Simpson Sand Depth to top 3818 Bottom 3827 Total Depth of Well 3850 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	240	Cemented
				5 1/2"	3847	3294'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled with sand from 3834 feet to 3574 feet. Ran 5 sacks of cement from 3575 feet to 3545 feet. Heavy mud to 240 feet and set plug at 240 feet. Rock from 240 feet to 230 feet and 4 sacks of cement. Tried to bail out water but cement did not set so ran 4 more sacks of cement. Bailed out water and ran 17 more sacks of cement from 230 feet to 155 feet. Mudded from 155 feet to 40 feet. Rock from 40 feet to 30 feet. Ran 10 sacks of cement from 30 feet to base of cellar.

RECEIVED  
STATE CORPORATION COMMISSION

NOV 24 1965

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Glenn and Smith Pipe Pulling Company  
Address Box 156, Ellinwood, Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss.  
Dwight J. Wilson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
800 Biting Building, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 23rd day of November, 1965

My commission expires August 10, 1969  
Virginia Mundell Notary Public

WELL LOG

ALPINE OIL & ROYALTY CO., INC.

Commenced: January 23, 1964

Contractor: Quaker Drilling Co., Inc.

Completed: February 2, 1964

No. 1 Wright  
SE SW NE Sec. 35-22S-14W  
Stafford County, Kansas

Elevation: 1933 K. B.

Casing Record:

Set 8 5/8ths inch casing at 240 feet with 200 sacks of cement  
Set 5 1/2 inch casing at 3847 feet with 125 sacks of cement

(Figures Indicate the Bottom of the Formations)

<u>FORMATION</u>	<u>DEPTH</u>	<u>FORMATION TOPS</u>	
Surface Soil and Sand	180	Anhydrite	842 +1091
Blue Shale and Shells	241	Heebner	3330 -1397
Red Bed	285	Brown Lime	3460 -1527
Sand	842	Lansing	3474 -1541
Anhydrite	870	Base Kansas City	3683 -1750
Shale and Shells	1625	Viola	3755 -1822
Lime and Shale	3475	Simpson	3796 -1863
Lime	3750	Arbuckle	3844 -1911
Cherty Lime	3800	Rotary Total Depth	3850 -1917
Lime	3830		
Shale, Sand and Lime	3850		

RECEIVED  
STATE CORPORATION COMMISSION

NOV 10 1965

CONSERVATION DIVISION  
Wichita, Kansas

We hereby certify the foregoing to be a true and correct copy of the driller's log of the well drilled in the SE SW NE of Section 35, Township 22 South, Range 14 West, Stafford County, Kansas.

QUAKER DRILLING CO., INC.

By:   
Dwight J. Wilson

Subscribed and Sworn to before me a Notary Public this 25th day of February, 1964.

  
Virginia Mundell, Notary Public

MY COMMISSION EXPIRES:  
August 10, 1965