


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Stafford County. Sec. 35 Twp. 22 Rge. (E) 14 (W)

NORTH



Locate well correctly on above  
Section Plat

Location as "NE/CNW/SW" or footage from lines NW NE NE  
Lease Owner Tennessee Gas Transmission Company  
Lease Name John Donald Wright Well No. 1  
Office Address P. O. Box 163 - Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed 8-28 19 57  
Application for plugging filed 8-27 19 59  
Application for plugging approved 8-31 19 59  
Plugging commenced 8-31 19 59  
Plugging completed 9-8 19 59  
Reason for abandonment of well or producing formation Lease Uneconomical To  
Produce  
If a producing well is abandoned, date of last production 7-18 19 59  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot  
Producing formation Lansing Depth to top 3583 Bottom 3589 Total Depth of Well 3884 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	373'	none
				5-1/2"	3884'	3383'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Checked the hole to 3604' and found it open.  
Filled w/sand to 3570' and dumped 5 sacks of cement with bailer. Pulled 5 1/2" casing.  
Cleared hole and bailed fluid to 340' used 8 sacks of gel mud and mudded the hole to 300', set rock bridge to 290' and dumped 20 sacks of cement. Mudded the hole to 40', set rock bridge to 30' and ran 10 sacks of cement to base of cellar.

Plugging Completed

Name of Plugging Contractor Knights Casing Pulling Company (If additional description is necessary, use BACK of this sheet)  
Address Chase, Kansas

STATE OF KANSAS COUNTY OF BARTON, ss.  
Glen E. Armour (employee of owner) ~~or (owner) or (operator)~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Glen E. Armour  
P. O. Box 163 - Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 10th day of September, 19 59

My commission expires October 13, 1962

John Lemons  
Notary Public.

PLUGGING  
FILE SEC 35 T 25 R 14W  
BOOK PAGE 63 LINE 36

COMPANY: Tennessee Gas Transmission Company  
Chase, Kansas

Rotary Drilling Commenced: 1-8-57  
Rotary Drilling Completed: 1-22-57

LOCATION: John Donald Wright #1  
NW NE NE 35-22S-14W  
Stafford County, Kansas

CONTRACTOR: Shelley-Miller Drilling Company  
205 Miller Building  
Wichita, Kansas

CASING RECORD: 8 5/8 24# casing set @ 373', cemented with  
250 sacks cement.  
5 1/2 14# casing set @ 3884, cemented with 110  
sacks cement.

LOG

(Measurements from top of Rotary Bushing to bottom of formation)

Sand and Shale	373
Red Bed and Shale	800
Red Bed	839
Anhydrite	880
Shale and Shells	1,720
Lime and Shale	3,470
Lime	3,884 Rotary T.D.

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 14 1959  
CONSERVATION DIVISION  
Wichita, Kansas

The undersigned, Richard A. Shelley, Partner of Shelley-Miller Drilling Company, hereby certifies in behalf of said company, that the above log is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

SHELLEY-MILLER DRILLING COMPANY

By *Richard A. Shelley*

STATE OF KANSAS )  
COUNTY OF SEDGWICK ) SS

BE IT REMEMBERED, that on this 29th day of January, 1957, before me, the undersigned, a Notary Public, duly commissioned in and for the county and state aforesaid, came Richard A. Shelley, Partner, and known to me to be the same person who executed the foregoing instrument of writing in behalf of Shelley-Miller Drilling Company, as a Partner of said company, and he duly acknowledged the execution of the same for himself and for said company.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal on the day and year above written.

*Leona M. Towers*  
Notary Public

My Commission Expires:  
March 24, 1960

PLUGGING  
FILE SEC. 35 T. 25 R. 14W  
BOOK PAGE 63 LINE 36

2-70  
1-DN  
2-WJ