


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give ALL Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

STAFFORD County, Sec. 29 Twp. 22 Rge. (E) 14 (W)
Location as "NE/CNW/SSW" or footage from lines NE NE NE
Lease Owner SANTA-FE PIPE & SUPPLY, INC.
Lease Name MC MILLAN Well No. 1
Office Address BOX 562 - GREAT BEND, KANSAS 67530
Character of Well (completed as Oil, Gas or Dry Hole) OIL
Date well completed JULY 6 19 58
Application for plugging filed AUGUST 28 19 69
Application for plugging approved AUGUST 29 19 69
Plugging commenced SEPTEMBER 2 19 69
Plugging completed NOVEMBER 8 19 69
Reason for abandonment of well or producing formation DEPLETED

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well R. W. WARREN
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4023' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	240'	NONE
				5 1/2"	3775'	1506.98'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

4023'	-	3750'	-	PLUG
3750'	-	3630'	-	SAND
3630'	-	3590'	-	5 SACKS CEMENT
3590'	-	225'	-	MUD
225'	-	BASE	-	PUMPED 10 SACKS GEL MUD AND 75 CEMENT

RECEIVED
STATE CORPORATION COMMISSION
DEC 10 1969
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor SANTA-FE PIPE & SUPPLY, INC.
Address BOX 562 - GREAT BEND, KANSAS

STATE OF KANSAS COUNTY OF BARTON, ss.
T. L. NUTT (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) T. L. Nutt

BOX 562 - GREAT BEND, KANSAS
(Address)

SUBSCRIBED AND SWORN to before me this 9th day of DECEMBER, 19 69

My commission expires JULY 31, 1970
Mary M. Guesnier
Mary M. Guesnier Notary Public.

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

15-185.00472-0000


COPY

Company- HILTON DRILLING COMPANY
Farm- McMillan No. 1

SEC. 29 T. 22 R. 14W
NE NE NE

Total Depth. 4023'
Comm. 6-21-58 Comp. 7-6-58
Shot or Treated.
Contractor. Hilton Drilling Co., Inc.
Issued. 11-1-58

County Stafford
KANSAS



CASING:
8 5/8" @ 241' w/200 sx.
5 1/2" @ 3775' w/100 sx.

Elevation. 1958' KB

Production. 76 BOED, 11% Wtr.

Figures Indicate Bottom of Formations.

sand & clay	70
sand	110
shale & rock	160
shale & shells	330
shale	360
sand	440
red bed & shells	880
anhydrite	920
shale & shells	1525
shale & lime	1775
lime	2155
shale & lime	2795
lime	2805
lime & shale	2850
lime	2900
lime & shale	3080
lime	3210
lime & shale	3280
lime	3401
lime & shale	3460
shale & shells	3512
lime	3751
conglomerate	3778
lime	3893
lime & chert	3914
lime	3970
lime & shale	4014
lime	4023
Total Depth	

TOPS: (Scout)	
Heebner	3385
Toronto	3405
Lansing	3520
Viola	3866
Simpson	3942
Arbuckle	4005

RECEIVED
STATE CORPORATION COMMISSION
AUG 29 1969
CONSERVATION DIVISION
Wichita, Kansas