

15-185-21721-0000

WELL PLUGGING RECORD

Give All Information Completely  
 Make Required Affidavit

COUNTY Stafford SEC. 29 TWP. 22 RGE. 14 E/W  
 Location as in quarters or footage from lines:  
SE/SW/SE


Locate Well  
 correctly on above  
 Section Platt.

Lease Owner Mustang Drilling & Exploration, Inc.  
 Lease Name Symms Well No. #1  
 Office Address Box 1609 - Great Bend, Kansas 67530  
 Character of Well (Completed as Oil, Gas or Dry Hole): Oil  
 Date Well Completed \_\_\_\_\_  
 Application for plugging filed \_\_\_\_\_  
 Plugging commenced September 08, 1983  
 Plugging completed September 21, 1983  
 Reason for abandonment of well or producing formation  
Depleted

Was permission obtained from the Conservation Division or it's  
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well J. H. Metz  
 Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom T.D. 4060'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8"	402'	NONE
				4 1/2"	4058'	2914.50'

Describe in detail the manner in which the well was plugged, indicating where the mud  
 fluid was placed and the method or methods used in introducing it into the hold. If cement  
 or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
 to \_\_\_\_\_ feet for each plug set.

Dumped sand to 3900' and four (4) sacks cement. Shot casing at 3500', 3200' and 3000'.  
Pulled seventy-two (72) joints of 4 1/2" casing.  
Sun squeezed well with four (4) sacks hulls, fifteen (15) sacks gel, fifty (50) sacks cement, fifteen (15) sacks gel, released plug and pumped one hundred twenty-five (125) sacks 60/40 pozmix cement with 2% added gel and 3% calcium chloride. Maximum pressure was 600 psi and shutin at 200 psi.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rockhold Engineering, Inc.


STATE OF KANSAS COUNTY OF BARTON, ss.  
James W. Rockhold (employee of owner) or (owner or operator) of the  
 above-described well, being first duly sworn on oath, says: That I have knowledge of the  
 facts, statements, and matters herein contained and the log of the above-described well as  
 filed and that the same are true and correct. So help me God.

(Signature) James W. Rockhold  
 JAMES W. ROCKHOLD - Box 698 - Great Bend, Ks.  
 (Address) 67530

SUBSCRIBED AND SWORN TO before me this 30<sup>th</sup> day of Sept., 1983

Jo A. Dewell  
 Notary Public.

My Commission expires:



RECEIVED  
 STATE CORPORATION COMMISSION

OCT 3 1983