

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-185-22965-0000

LEASE NAME McMillan

WELL NUMBER #1

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

1650 Ft. from S Section Line

3630 Ft. from E Section Line

SEC. 29 TWP. 22S RGE. 14W ~~XXXXX(W)~~

COUNTY Stafford

LEASE OPERATOR Oil Producers, Inc. of Kansas

P. O. Box 8647

ADDRESS Wichita, Kansas 67208

PHONE (316) 681-0231 OPERATORS LICENSE NO. 8061

Date Well Completed 6-14-94

Plugging Commenced 3:45 AM,
6-14-94

Plugging Completed 4:30 AM,
6-14-94

Character of Well _____

(Oil, Gas, O&A, SWO, Input, Water Supply Well)

The plugging proposal was approved on June 13, 1994 (date)

by Steve Pfeifer (KCC District Agent's Name).

Is AGO-1 filed? _____ If not, is well log attached? Yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.O. 3682'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	312' K.B.	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, -from ___ feet to ___ feet each set

Heavy mud to 910' with 50 sacks; heavy mud to 340' with 50 sacks; heavy mud to 40' with 10 sacks to surface; 15 sacks in rathole. Used 60/40 Pozmix with 6% gel. All plugs were spotted through open ended drill pipe.

Name of Plugging Contractor Sterling Drilling Company License No. 5142

P. O. Box 129

Address Sterling, Kansas 67579-0129

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Oil Producers, Inc. of Kansas

STATE OF KANSAS COUNTY OF RICE, ss.

Richard L. Mead (Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts stated herein, and matters herein contained and the log of the above-described well, and that the same are true and correct, so help me God.

(Signature) Richard L. Mead
Richard L. Mead, Vice President

(Address) P. O. Box 129, Sterling, KS 67579-0129

SUBSCRIBED AND SWORN TO before me this 15th day of June, 19 94

Cheryl R. Davis
Notary Public

My Commission Expires: 2-15-97

USE ONLY ONE SIDE OF EACH FORM



Form CP-1
Revised 05-88

STERLING DRILLING COMPANY

BOX 129

STERLING, KANSAS 67579

(316) 278-2131

SAMPLE LOG ----- MCMILLAN #1

Located: SW NE SW of Sec. 29-22S-14W,
Stafford County, Kansas

OWNER: OIL PRODUCERS INC OF KANSAS

ROTARY DRILLING CONTRACTOR: STERLING DRILLING COMPANY

COMMENCED: June 10, 1994

COMPLETED: June 14, 1994

TOTAL DEPTH: 3682' Driller

LOG

- 0' - 160' Surface Soil and Clay
- 160' - 315' Blue Shale and Red Bed
- 315' - 887' Shale
- 887' - 905' Anhydrite
- 905' - 1500' Shale
- 1500' - 3682' Shale and Lime

CASING RECORD

Spud at 10:45 AM, 06-10-94. Drilled 315' of 12 1/4" hole. Ran 7 joints 8 5/8" casing. 300.18' pipe set at 312' K.B. Cemented with 180 sacks 60/40 Pozmix with 2% gel and 3% cc. Plug down at 4:30 PM, 06-10-94 by Allied. Good returns. Ticket No. 6563.

Plugged.

DEVIATION SURVEY

1/2° at 315'

RECEIVED
STATE CORPORATION COMMISSION

JUN 17 1994

CONSERVATION DIVISION
Wichita, Kansas