

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
July 2014
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 4624
Name: Uihlin, Ted Oil Properties
Address 1: 2407 Whitehall Manor
Address 2: _____
City: Lawrence State: KS Zip: 66044 + _____
Contact Person: J.C. Hawes
Phone: (620) 342-1148
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
McLouth SD UPR Depth to Top: 1532 Bottom: 1544 T.D. 1612
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 087-20407-00-00
Spot Description: _____
S/2 SW SW Sec. 9 Twp. 10 S. R. 20 East West
70 Feet from North / South Line of Section
4,950 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Jefferson
Lease Name: Sanders Well #: 2
Date Well Completed: 6/25/1988
The plugging proposal was approved on: 11/21/2016 (Date)
by: Taylor Herman (KCC District Agent's Name)
Plugging Comenced: 1/10/2017
Plugging Completed: 1/11/2017

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
McLouth Sand	Oil	Surface	7.6250	257	0
		Production	4.5000	1610	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

2-3/8" tubing RIH to 1500 ft., displaced fluid with gel, pumped 50 ft. cement plug 1500 ft. to 1450 ft., pulled tubing up to 700 ft, displaced balance of fluid in 4-1/2" with gel, pumped 50 ft. cement plug from 700 ft. to 650 ft., pulled tubing up to 325 ft., circ cement to surface, pulled tubing out of hole, topped off 4-1/2", RIH between 4-1/2" and 7" w/ 1/2', tagged TOC at 30 ft., topped off.

Received
KANSAS CORPORATION COMMISSION
JAN 17 2017
CONSERVATION DIVISION
WICHITA, KS

Plugging Contractor License #: 5721 Name: Glacier Petroleum, Inc.
Address 1: P.O. Box 577 Address 2: _____
City: Emporia State: Kansas Zip: 66801 + 0577
Phone: (620) 352-1148
Name of Party Responsible for Plugging Fees: Glacier Petroleum, Inc.
State of Kansas County, Lyon, ss.
J.C. Hawes Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: J.C. Hawes

