

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-155-19040-0001

LEASE NAME Snowbarger "B"

WELL NUMBER 4

SPOT LOCATION C W/2 NE/4

SEC. 21 TWP. 23 RGE. 10 (E) or (W) W

COUNTY Reno

Date Well Completed 11-11-41

Plugging Commenced 3-12-84

Plugging Completed 3-13-84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Fell Oil and Gas Co.

ADDRESS P.O. Box 9487 Tulsa, OK 74157

PHONE # (918) 446-6114 OPERATORS LICENSE NO. 6718

Character of Well SWD
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District #2

Is ACO-1 filed? No If not, is well log attached? Yes

Producing formation _____ Depth to top _____ bottom _____ T.D. 4644

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
<u>Viola</u>	<u>Water</u>	<u>3776</u>	<u>96</u>	<u>10 3/4</u>	<u>190</u>	<u>None</u>
<u>Granite Wash</u>	<u>Water</u>	<u>4600</u>	<u>44</u>	<u>7</u>	<u>3771</u>	<u>None</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Pumped 100 sacks cement between 10 3/4 surface pipe and 7 casing. Then pumped 100 sacks cement down 7" casing. Could not get down casing to clean out or pull 7". Witnessed by Ed Wiskoff of KCC.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Gressel Oil Field Service License No. 5823
Address P.O. Box 286
Burrton, KS

STATE OF OKLAHOMA COUNTY OF TULSA, ss.

BRUCE L. TATON (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

STATE CORPORATION COMMISSION

(Signature) Bruce L. Taton

(Address) P.O. Box 9487

Tulsa, OK 74157

MAY 16 1984

SUBSCRIBED AND SWORN TO before me this 14th day of May, 19 84
Wichita, Kansas

Gloria A. Sam
Notary Public
Gloria A. Sam

My Commission expires: 2/14/88

DRILLING LOG

REPUBLIC NATURAL GAS COMPANY
Lease Snowbarger
Well No. 4

County Reno
Sec. 21 Twp. 23 Rge. 10
Location SW NW NE
Elevation 1779'

Total Depth 3809'
Comm. 10-4-41 Comp. 11-11-41
Shot or Treated Treated

CASING:

170' - 10 3/4" OD
3771' - 7" OD

Contractor Simpson & Noble
Rotary T. D. 3779'
Cable Tools From 3779' To 3809'

Figures Indicate Bottom of Formations:

0 - 190	Red Bed
190 - 445	" "
445 - 475	Anhydrite
475 - 500	Shale & shells
500 - 1025	" " "
1025 - 1070	Salt
1070 - 1375	Salt & Shale
1375 - 1440	Shale & shells
1440 - 1594	Lime
1594 - 1808	Shale & Lime Shells
1808 - 1908	Broken Lime & Shale
1908 - 2039	" "
2039 - 2172	" "
2172 - 2304	" "
2304 - 2400	Shale
2400 - 2497	"
2497 - 2618	Shale, Lime breaks
2618 - 2654	Shale
2654 - 2778	Shale & Broken Lime
2778 - 2871	Broken Lime - Shale
2871 - 2918	Broken Lime
2918 - 3000	Lime & Broken Lime
3000 - 3088	Shale & Broken Lime
3088 - 3171	Broken Lime
3171 - 3225	" "
3225 - 3322	" "
3322 - 3400	K. O. Lime

3400 - 3450	Lime
3450 - 3525	Broken Lime
3525 - 3573	Lime
3573 - 3633	Broken Lime
3633 - 3643	" "
3643 - 3670	" " & Chert
3670 - 3681	Shale
3681 - 3740	"
3740 - 3776	"
3776 - 3778	Viola Lime
3778 - 3779	Cemented casing
3781 - 3784	Lime
3784 - 3786	"
3786 - 3792	"
3792 - 3796	"
3796 - 3804	"
3804 - 3806	"
3809 -	Steel Line Measure - T.D.
	Plugged back to 3783
3783 - 3788	

Deepening Job.
Started - 5-15-1943
Comp. 7-4-1943
Cable Tools.
3788-3809 - Cement
3809-3816 - Lime

(SEE OVER FOR CORING RECORD)

RECEIVED
STATE CORPORATION COMMISSION

MAY 16 1984

CONSERVATION DIVISION
Wichita, Kansas