

15-155-02244-0000

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Reno County, Sec. 21 Twp. 23 Rge. 10 (E) W (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NW $\frac{1}{4}$ NW $\frac{1}{4}$ NE $\frac{1}{4}$

Lease Owner Republic Natural Gas Company

Lease Name Snowbarger "B" Well No. 3

Office Address Box 126, Ellinwood, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed September 28 19 51

Application for plugging filed November 1 19 51

Application for plugging approved November 3 19 51

Plugging commenced November 8 19 51

Plugging completed November 17 19 51

Reason for abandonment of well or producing formation Formation depleted

If a producing well is abandoned, date of last production October 24 19 51

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives

Producing formation Viola Depth to top 3764' Bottom Total Depth of Well 3783 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Surface casing			185'	8-5/8"	185'	None
Oil string casing			3764'	5 1/2"	3764'	3101'
Viola	Oil	3764'	3783'			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

3783 - 3760 Sand
3760 - 3718 Cement, 6 sacks
3718 - 235 Heavy mud
235 - 225 Permanent rock bridge
225 - 172 Cement, 35 sacks
172 - 25 Heavy mud
25 - 15 Rock bridge
15 - Bottom of cellar Cement, 5 sacks

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Pipe Pulling, Inc.

Address 629 W. Broadway, Stafford, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.

H. E. Wolfe (employee of owner) or (owner/operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *H. E. Wolfe*

Box 126 Ellinwood, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 28th day of November, 1951

My commission expires 8-20-55

Yvonne M. Stevenson
Notary Public

PLUGGING
FILE SEC 21 T 23 R 10
COOK PAGE 12 LINE 45

NOV 29 1951
CONSERVATION DIVISION
Wichita, Kansas

Drilling Log

15-155-02244-0000

Company: Republic Natural Gas Company
Contractor: Simpson & Noble Drilling Co.
Farm: Snowbarger "B"
Well: #3
Location: NW/4 NW/4 NE/4 Section 21-23-10
Reno County, Kansas
Completed: 9-28-41

0 - 185	Clay & Sand
185 - 443	Red Beds
443 - 460	Anhydrite
460 - 600	Red Bed
600 - 875	Blue & Brown Shale
875 - 1030	Shale & Shells
1030 - 1209	Salt
1209 - 1703	Shale & Shells
1703 - 1932	Lime
1932 - 1952	Shale
1952 - 2030	Broken Lime
2030 - 2122	Lime
2122 - 2210	Broken Lime
2210 - 2273	Shale & Shells
2273 - 2890	Broken Lime
2890 - 3017	Lime
3017 - 3074	Broken Lime
3074 - 3180	Lime
3180 - 3216	Shale
3216 - 3264	Shale & Lime, Shells
3264 - 3312	Shale & Shells
3312 - 3403	K. C. Lime
3403 - 3485	Lime
3485 - 3657	Broken Lime
3657 - 3765	Shale
3765 - 3783	Lime
3783	T.D.

PLUGGING
FILE SEC-21-23-10
BOOK PAGE 121 LINE 45

RECEIVED
STATE CORPORATION COMMISSION
NOV - 3 1951
CONSERVATION DIVISION
Wichita, Kansas

