

15-55-01494-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Reno County, Sec. 21 Twp. 23 Rge. 10 (E) W. (W)

Location as "NE/CNWxSWx" or footage from lines NE SE SW

Lease Owner Cities Service Oil Company

Lease Name Kreie "D" Well No. 2

Office Address Box 144, Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil Well

Date well completed January 23, 1942

Application for plugging filed March 14, 1957

Application for plugging approved March 15, 1957


Plugging commenced April 22, 1957

Plugging completed April 27, 1957

Reason for abandonment of well or producing formation Depleted formation.

If a producing well is abandoned, date of last production March 1, 1957

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Ruel Durkee

Producing formation Viola Depth to top 3763 Bottom 3777 Total Depth of Well 3777 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	240'	None
				5-1/2"	3765'	1623'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

- 3777-3755', river sand.
- 3755-3707', 6 sacks cement.
- 3707- 230', heavy mud.
- 230- 170', rock bridge and 15 sacks cement.
- 170- 25', heavy mud.
- 25' to base of cellar, rock bridge and 5 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor G. E. Shull Casing Pulling Company

Address Great Bend, Kansas

STATE OF Kansas COUNTY OF Barton ss.  
V. M. Conover (employee of owner) or owner or operator

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) V. M. Conover

Box 144, Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 30th day of April 19 57

W. D. Smith Notary Public.

My commission expires March 12, 1959.

PLUGGING  
FILE SEC 21 T 23 R 10W  
BOOK PAGE 148 LINE 8

MAY 2 - 1957 5-2-57  
CONSERVATION DIVISION  
Wichita, Kansas

Company Cities Service Oil Co. Well No. 2 Farm Kreie "D"  
 Location 990' N. & 330' W. of S/4 Corner Sec. 21 T. 23 R. 10W  
 Elevation 1785 County Reno State Kansas  
 Drlg. Comm. December 20, 1941 Contractor Hiasom Drilling Company  
 Drlg. Comp. January 23, 1942 Acid 500 gals. Jan. 24, 1942  
 T. D. 3777' Initial Prod. B. H. P. Gauge Potential: 3000 oil, no water, 24 hours  
 (Ind. Cap. 40,984 bbls.)

CASING RECORD:

8-5/8" @ 240' con. 200 ex Ash Grove  
 5-1/2" @ 3765' con. 75 ex Cement

Corr. Top Viola 3763'  
 Penetration 14'  
 Total Depth 3777'

FORMATION RECORD:

sand 0-120  
 red bed & shale 240  
 red bed, shale & shells 750  
 shale & lime shells 1468  
 shale & sandy lime shells 1580  
 shale & lime shells 1695  
 broken lime & shale 1869  
 broken sandy lime & shale 2000  
 shale & lime shells 2220  
 broken lime & shale 2405  
 shale & lime shells 2550  
 shale & broken lime shells 2680  
 broken lime 2887  
 lime 3124  
 broken lime 3308  
 lime 3400  
 broken lime & shale 3441  
 lime 3545  
 broken lime 3582  
 lime 3645  
 shale 3734  
 shale & lime shells 3750  
 shale 3768  
 lime 3770  
 3770 Rot. TD = 3765 SLM  
 lime 3777 T. D.

Loaded hole with 2500' water  
 before drilling in. No fillup.  
 Good show oil 3772-77.

Syfo: 500' 0°  
 1000' 0°  
 1500' 0°  
 2000' 0°  
 2500' 0°  
 3000' 0°

RECEIVED  
 STATE DEPARTMENT  
 WICKI...

CONNECTION DIVISION  
 Wichita, Kansas

PLUGGING  
 FILE SEC 21 T. 23 R. 10W  
 BOOK PAGE 148 LINE 8