

R

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

AUG 12 1965

CONSERVATION DIVISION
Wichita, Kansas

8-12-65

Operator's Full Name Petroleum, Inc.

Complete Address: 352 N. Broadway, Wichita, Kansas

Lease Name Milton "B" Well No. # 1

Location NW NW NE Sec. 32 Twp. 22 Rge. 13 (E) (W) W

County Stafford Total Depth 3900'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: This hole was a wash down

Plugging Contractor: Garvey Drilling Company

Address: R. R. # 2, Great Bend, Kansas License No. _____

Operation Completed: Hour 5:00 PM Day 8th Month August Year 1965

The Above well was plugged as follows:

220' of 8 5/8" surface pipe, cement circulated. Fluid was up in the hole.
1st cementing plug and 1/2 sack of hulls was pushed in fluid to 220', and
cemented with 25 sacks, through the drill pipe. Hole was filled with
drilling mud to 40', 2nd cementing plug, bridged solid with hulls on
fluid at 40', and cemented with 10 sacks to the base of the cellar.
Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 8-12-65

INV. NO. 1620-W

Signed: Archie Elving
Well Plugging Supervisor