

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 185 - 00470 - 0000 (of this well)

Operator's Full Name Mobil Oil Corp.

Complete Address Box 5444, Denver, Colo. 80217

Lease Name Fair "B" Well No. 1

Location NW SE SW Sec. 4 Twp. 22 Rge. 11(E) (W) X

County Stafford Total Depth 3586

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Kelso Casing Pulling.

Address Box 176, Chase, Ks. 56524 License No. 683

Operation Completed: Hour 12:30 Pm Day 9 Month 6 Year 1980

The above well was plugged as follows:

301' 8 5/8" casing w/175 sax cement. 5 1/2" casing set at 3583' w/150 sax
cement. Bridge at 3154'-Top preforated at 3194'-Sand back to 3054'-
Top sand w/ 5 sax mixed cement w/dump bailer. Pull 2355' casing.
Howco mixed & pumped 8 sax hulls-25 sax gel-100 sax 50/50 posmix
cement w/4% gel & 3% cc to top of casing. Shut in w/300# pressure.
(Pipe was shot off at 2704'-1949'-1911'-1787'-1728'-1600').

6-11-80

RECEIVED

JUN 21 1980

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED

DATE 6-11-80

INV. NO. 2333w