

15-185-01216-0001

Form CP-3
Rev. 6-26-62

le
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

APR 8 1963

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Inger Oil Co.

Complete Address: 1020 Central Bldg., Wichita, Kansas

Lease Name Durham Well No. # 1

Location NW SW NE Sec. 33 Twp. 22 Rge. 13 (E) (W) W

County Stafford Total Depth 3647

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling

Address: Box 304, Chase, Kansas License No. 436

Operation Completed: Hour 9:30AM Day 4th Month April Year 1963

The Above well was plugged as follows:

285' of 8 5/8" surface pipe cement circulated. 3647' of 5 1/2" long string
cemented with 100 sacks. Top perferation 3531', squeezed at 2500', plug
at 3450'. Fluid in hole was at 60', would not bail down. An over night
plug was set on rock bridge with 4 sacks cement at 200'. Next morning
fluid bailed down and a total of 20 sacks was set on plug. Hole filled
to 40' with mud, 10' rock bridge, 10 sacks cement to base cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 4/8/63
INV. NO. 6854W