

R

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

AUG 12 1965

CONSERVATION DIVISION
Wichita, Kansas

8-12-65

Operator's Full Name Donald T. Ingling

Complete Address: 615 First National Bank Bldg., Wichita, Kansas

Lease Name Hallman Well No. # 1

Location NW NW NW Sec. 36 Twp. 22 Rge. 13 (E) (W) W

County Stafford Total Depth 2890'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Donald T. Ingling Drilling Company

Address: 615 First National Bank Bldg., Wichita, Ks License No. _____

Operation Completed: Hour 11:00 PM Day 9th Month August Year 1965

The Above well was plugged as follows:

287' of 8 5/8" surface pipe, cement circulated with 250 sacks. Fluid
level in the hole was at 250', 1st cementing plug, bridged solid with
hulls on fluid at 250', and cemented with 25 sacks. Hole was filled
with drilling mud to 40', 2nd cementing plug, bridged solid with hulls
on fluid at 40', and cemented with 10 sacks to the base of the cellar.
Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 8-12-65

INV. NO. 1623-W