

P

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 145 - 20,563 - 0000 (of this well)

Operator's Full Name Alpine Drlg. & Husky Drlg.

Complete Address 800 Bitting Bldg., Wichita, Ks.

Lease Name Miller "A" Well No. 1

Location NW SE SW Sec. 23 Twp. 22 Rge. (E) (W) 15

County Pawnee Total Depth 4045'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor ~~ASSOCIATED INDUSTRIES~~ Husky Drlg.

Address Wichita, Ks. License No.

Operation Completed: Hour 11 A Day 24 Month 1 Year 1979

The above well was plugged as follows:

RTD 4045' 8 5/8 csg set 290' cwc Plg. Mat. 50-50 poz 2% total gel.

Gunned pits, circulated heavy mud, set 50 sk cmt plug at 420' thru drill pipe.

Heavy mud to 240' set 25 sk cmt plug thru drill pipe. Heavy mud to 40' set solid
bridge & 10 sk cmt plug to base of cellar.

RECEIVED 1-25-79
STATE CORPORATION COMMISSION

JAN 25 1979

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 1-30-79
INV. NO. 9033-W

CONSERVATION DIVISION
Wichita, Kansas
Signed: Leo T. Massey
Well Plugging Supervisor