

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

AUG 21 1973

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name O. A. Sutton

Complete Address 800 Sutton Place, Wichita, Kansas

Lease Name Lewis Well No. 1

Location NE SE NW Sec. 23 Twp. 22 Rge. (E) (W) 15

County Pawnee Total Depth 4030'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated _____

Plugging Contractor Gabbert-Jones Drlg.

Address Wichita, Kansas License No. _____

Operation Completed: Hour 2:30 P Day 18 Month 8 Year 1973

The above well was plugged as follows:

RTD 4030' 8 5/8 csg set at 268' cwc 225 sk.

Gunned pits, circulated heavy mud, set cementing plug at 690' and displaced 50 sk

cmt thru drill pipe. Heavy mud to 240' set cementing plug and displaced 25 sk cmt

thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to

base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Z. Massey
Well Plugging Supervisor

DATE 8/22/73
INV. NO. 7806-4