

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT **RECEIVED**
STATE CORPORATION COMMISSION
SEP 19 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Barnett Oil Company

Complete Address: 411 First Nat'l Bk. Bldg., Wichita, Kansas

Lease Name Wilson Well No. 1

Location NE SW SW Sec. 21 Twp. 22 Rge. 15 (E) (W) X

County Pawnee Total Depth 3990'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Hellar Drlg

Address: Wichita, Ks. License No. _____

Operation Completed: Hour 8A Day 17 Month 9 Year 1968

The Above well was plugged as follows:

RTD 3990' 8 5/8 csg set at 248' cwc 175 sc. Cem. Mat. 100 sc of 6% 50-50 poz.

Gypped pits, circulated heavy mud, set cementing plug at 540' and displaced 70 sc cem.

thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sc cement thru

drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base

of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo A. Messing
Well Plugging Supervisor

DATE 9/19/68
INV. NO. 8479-4