

KANSAS

Form CP-3
Rev. 6-4-68STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORTRECEIVED
STATE CORPORATION COMMISSION

SEP 08 1975

CONSERVATION DIVISION
Wichita, KansasJ. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Phillips Petroleum Company

Complete Address P. O. Box 287, Great Bend, Kansas 67530

Lease Name Bowman "B" Well No. 1

Location SE NE SE Sec. 31 Twp. 22 Rge. (E) (W) 15

County Pawnee Total Depth 3980'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Knight Casing Pulling

Address Box 405, Chase, Kansas 67524 License No. 436

Operation Completed: Hour 3:30 P Day 5 Month 9 Year 1975

The above well was plugged as follows:

Total Depth 3980' 8 5/8 csg set 341' cwc 275 sk.5 1/2 csg set 3716' cw 100 sk cem.5 1/2 csg PBTD 3647' & PFS (3628-3632)Filled 5 1/2 csg W/sd (3600-3647) Dumped 5 sk cem W/dump bailer. (3600-3565)Cutoff & recovered 2333' of 5 1/2 csg.Pumped down 8 5/8 csg with 25 sk gel & water W/300 lbs hulls -released plug &pumped 125 sk 60-40 poz by Halliburton Cementing Co. PP 600 lbs. SIP 400 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Marsuff
Well Plugging SupervisorDATE 9-9-75INV. NO. 1882-W