

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

SEP 15 1975
9-15-75
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Phillips Petroleum Company

Complete Address P. O. Box 287, Great Bend, Kansas 67530

Lease Name Bowman "B" Well No. 2

Location NE SE SE Sec. 31 Twp. 22 Rge. (E) (W) 15

County Pawnee Total Depth 3628'

Abandoned Oil Well Gas Well XX Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Knight Casing Pulling

Address Box 405, Ghase, Kansas 67524 License No. 436'

Operation Completed: Hour 11 A Day 12 Month 9 Year 1975

The above well was plugged as follows:

Total Depth 3628' 8 5/8 csg set 380' cwc 200 sk.

5 1/2 csg set 3624' cw 75 sk cem.

5 1/2 csg perf. 3035' & squeezed W/200 sk cmt.

5 1/2 csg PBSD 3030' PFS (3017-3014) & (2983-2975)

Set 35 sk cmt plug (3030-2902) thru 2 1/2" tbg.

Cutoff & recovered 2150' of 5 1/2 csg.

Pumped down 8 5/8 csg with 25 sk gel & water W/300 lbs hulls -released plug &

pumped 125 sk 60-40 poz by HOWCO. PP 600 lbs. SIP 300 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 9-15-75
INV. NO. 1910-W

Signed: [Signature]
Well Plugging Supervisor