

DISTRICT CONSERVATION AGENT'S REPORT

B

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

15-155-19267-0000

FILE NO. 23-35

LOCATION C S/2 SW NE

SEC. 31 TWP. 23S RGE. 10W

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 6-A Lease Ira C. Johnson

Operator Stanolind O & G Co. Address Box 591, Tulsa, Oklahoma

Field Zenith County Reno

Total Depth 3725 Feet.

(Describe briefly the manner in which the well was plugged)

Filled with mud from total depth 3725' to

3710'. Dumped 5 sacks cement, filled from

3710' to 3680'. Ripped pipe at 2950' and

pulled. Filled with mud from 3680' to 265'

Dumped 15 sacks cement, filled from 265' to 240'.

Filled with mud from 240' to 15'. Dumped 10 sacks

cement and filled from 15' to bottom of cellar.

PLUGGING
FILE SEC 31 T 23 R 10W
BOOK PAGE 23 LINE 35

C. D. Stough JUN 1 - 1948
District Conservation Agent

Date May 6, 1948