

1 080516

214R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 185-22,369-0000

SW NW SW, SEC. 30, T 22 S, R 14 W EX

1650 feet from S section line

4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5313

Lease Name Compton "B" Well # 1

Operator: F & M Oil Co., Inc.

County Stafford 132.28

Name & Address 422 Union Center

Well Total Depth 4070 Arbuckle feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 523

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Union Drilling Co., Inc. License Number 5103

Address 422 Union Center, Wichita, KS 67202

Company to plug at: Hour: 2:00 am Day: 23 Month: April Year: 19 86

Plugging proposal received from Lyle Cason

(company name) Union (phone) 316-262-1872

Elevation 1980

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 913-934'

1st plug at 930' with 50 sx cement

2nd plug at 560' with 50 sx cement

3rd plug from 40' to surface with 10 sx cement

4th plug to circulate rathole with 15 sx cement

Plug water well with 5 sx cement

Plugging Proposal Received by Steve Durrant

(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 3:30 am Day: 23 Month: April Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 930' with 50 sx cement, 2nd plug at 560' with 50 sx

cement, 3rd plug from 40' to surface with 10 sx cement, 4th plug to circulate rat hole

with 15 sx cement. Plugged water well with 5 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

APR 2 9 1986

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel

(if additional description is necessary, use BACK of this form.)

INVOICED
did not observe this plugging.

Signed J. H. Mead (TECHNICIAN)

DATE MAY 05 1986

INV. NO. 13616 4-23

FORM CP-2/3
Rev. 01-84