

1052316

TO: STATE CORPORATION COMMISSION

API NUMBER 15-185-22,459 -00-01
SW NW NE SEC. 32, T 22 S, R 14 W

4-29

CONSERVATION DIVISION - PLUGGING SECTION 4290 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 2310 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME MCALLISTER WELL # 4

TECHNICIAN'S PLUGGING REPORT

COUNTY STAFFORD

OPERATOR LICENSE # 7383

WELL TOTAL DEPTH 4140 13458 FEET

OPERATOR: GRADY BOLDING CORPORATION PRODUCTION CSG: SIZE 5 1/2" @ 4075' WITH NA SX

NAME AND PO BOX 486 SURFACE CASING: SIZE 8 3/8" @ 305 WITH NA SX

ADDRESS ELLINWOOD, KS 67526

ABANDONED OIL WELL GAS WELL INPUT WELL INJ WELL D-25,915 D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR MIKE'S TESTING & SALVAGE, INC LICENSE NUMBER 31529

ADDRESS PO BOX 467, CHASE, KS 67524-0209

COMPANY TO PLUG AT: HOUR: 5:00 PM DAY: 29 MONTH: 04 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM MIKE KELSO

(COMPANY NAME) MIKE'S TESTING & SALVAGE (PHONE) 316-938-2945

WERE: OPEN HOLE 4075-4140

1ST PLUG SANDED TO 3700' AND 5 SX CEMENT. PACKER LEFT IN BOTTOM OF HOLE.

2ND PLUG AT 950' WITH 50 SX CEMENT AND 10 SX GEL.

3RD PLUG AT 330' WITH 40 SX CEMENT.

4TH PLUG AT 40' WITH 10 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY RICHARD LACEY

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART X NONE

OPERATIONS COMPLETED: HOUR: 6:30 PM DAY: 29 MONTH: 04 YEAR: 1999

ACTUAL PLUGGING REPORT

1ST PLUG SANDED TO 3700' AND 5 SX CEMENT. PACKER LEFT IN BOTTOM OF HOLE.

2ND PLUG AT 950' WITH 50 SX CEMENT AND 10 SX GEL.

3RD PLUG AT 330' WITH 40 SX CEMENT.

4TH PLUG AT 40' WITH 10 SX CEMENT.

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2320' OF 5 1/2" CASING.
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

INVOICED
I DID OBSERVE THIS PLUGGING.

SIGNED Richard W. Lacey
(TECHNICIAN) FORM CP-2/3

DATE 5-7-99 MAY 04 1999

5-4-99

INV. NO. 60924 CONSERVATION DIVISION
Kansas