

1052317

TO: STATE CORPORATION COMMISSION

4-29

API NUMBER 15-185-20,716-0000  
NE SE NW SEC. 32, T 22 S, R 14 W

CONSERVATION DIVISION - PLUGGING SECTION 3630 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 2970 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME MCALLISTER WELL # 2

TECHNICIAN'S PLUGGING REPORT

COUNTY STAFFORD 131.04

OPERATOR LICENSE # 7383

WELL TOTAL DEPTH 4032 FEET

OPERATOR: GRADY BOLDING CORPORATION PRODUCTION CSG: SIZE 4 1/2" @ 3805' WITH 125 SX

NAME AND PO BOX 486 SURFACE CASING: SIZE 8 5/8" @ 290' WITH 225 SX

ADDRESS ELLINWOOD, KS 67526

ABANDONED OIL WELL X GAS WELL INPUT WELL INJ WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR MIKE'S TESTING & SALVAGE, INC LICENSE NUMBER 31529

ADDRESS PO BOX 467, CHASE, KS 67524-0209

COMPANY TO PLUG AT: HOUR: 3:00 PM DAY: 29 MONTH: 04 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM MIKE KELSO

(COMPANY NAME) MIKE'S TESTING & SALVAGE (PHONE) 316-938-2945

WERE: PERFS AT 3691-98 3656-61

SANDED TO 3500 AND 4 SX CEMENT.

PUMP DOWN 8 5/8" WITH 300# HULLS - 10 SX GEL - 50 SX CEMENT - 10 SX GEL - 100# HULLS -

8 5/8" PLUG - 100 SX CEMENT. MAXIMUM PRESSURE AT 400 PSIG. SHUT IN WITH 300 PSIG.

PLUGGING PROPOSAL RECEIVED BY RICHARD LACEY

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 4:50 PM DAY: 29 MONTH: 04 YEAR: 1999

ACTUAL PLUGGING REPORT

SANDED TO 3500 AND 4 SX CEMENT.

PUMP DOWN 8 5/8" WITH 300# HULLS - 10 SX GEL - 50 SX CEMENT - 10 SX GEL - 100# HULLS -

8 5/8" PLUG - 100 SX CEMENT. MAXIMUM PRESSURE AT 400 PSIG. SHUT IN WITH 300 PSIG.

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2015' OF 4 1/2" CASING.  
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

INVOICED

RECEIVED

I (DID) OBSERVE THIS PLUGGING.

DATE 5-7-99

SIGNED Richard W. Lacey (TECHNICIAN) FORM CP-2/3

INV. NO. 60924

MAY 04 1999

5-4-99

CONSERVATION DIVISION Wichita Kansas