

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-21655-00-00
Spot: CSWSESE Sec/Twnshp/Rge: 32-22S-14W
330 feet from S Section Line, 990 feet from E Section Line
Lease/Unit Name: STANDISH Well Number: 1
County: STAFFORD Total Vertical Depth: 4080 feet

Operator License No.: 7383
Op Name: BOLDING, GRADY CORPORATION
Address: PO BOX 486
ELLINWOOD, KS 67526

Conductor Pipe: Size feet: 8/32.60
Surface Casing: Size 8.625 feet: 423 WITH 300 SX CMT
Production: Size 4.5 feet: 4079 WITH 150 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 05/02/2002 3:45 PM

Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: MONTY ANDREWS Company: MIKE'S TESTING & SALVAGE, INC. Phone: (620) 938-2537

Proposed Plugging Method: SAND TO 3950' & 4 SX CMT. 1ST PLUG AT 900' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 450' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: RICHARD LACEY
Date/Time Plugging Completed: 05/02/2002 5:00 PM

Witness Type: Plugging Operations 100% Witnessed (Complete)
KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PERFS AT 4005-15 & 4010-20'. SANDED BACK TO 3950' & PUT 4 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. SPOT PLUGS THROUGH 4 1/2" CASING. 1ST PLUG AT 900' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 450' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

RECEIVED
MAY 07 2002
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2430' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

Signed

Stephen J. Pfeifer
(TECHNICIAN)

INVOICE

DATE 5-7-02 MAY 06 2002

TRAIL NO. 2002061757

Form 512