

1-050320

R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 145-21,150-0000

C N/2 SE, SEC. 23, T 22 S, R 15 W/R
1980 ^{FSV} feet from ~~NE~~ SE Corner of
1320 ^{FEV} feet from ~~NE~~ SE Corner of

TECHNICIAN'S PLUGGING REPORT

Operator License # 9247

Lease Name Miller Well # 1

Operator: Cincris Energy Company

County Pawnee

Name & Address 4600 Camelot East

Well Total Depth 4023 130.75 feet

Great Bend, KS 67530

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 250

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Mohawk Drilling, Inc. License Number 6394

Address Box 1362, Great Bend, KS 67530

Company to plug at: Hour: 2:00 am Day: 26 Month: August Year: 19 84

Plugging proposal received from Terry Williams

(company name) Mohawk Drilling (phone) 316-692-4531

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 930' with 50 sx cement

2nd plug at 570' with 70 sx cement
solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 10 sx cement

6th plug to circulate mouse hole with 10 sx cement

Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 3:15 am Day: 26 Month: August Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 930' with 50 sx cement, 2nd plug at 570' with 70 sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement, 5th plug to circulate rat hole with 10 sx cement, 6th plug to circulate mouse hole with 10 sx cement.

Remarks: Used 60/40 Pozmix 2% gel 3% cc. by Buie

(If additional description is necessary, use BACK of this form.)

STATE CORPORATION COMMISSION

INVOICED

(check / did not) observe this plugging.

DATE 9-10-84

SEP 04 1984

Signed Richard W. Lacey
(TECHNICIAN)

INV. NO. 3600

CONSERVATION DIVISION
Wichita, Kansas

9-4-84