

1 070403

SEP 5 1987

API NUMBER 15-145-21,264-0000

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NW SW SE, SEC. 21, T 22 S, R 15 W/E
990 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6718

Lease Name K.U. Endowment Well # 1

Operator: Fell Oil & Gas
Name & Address: 4451 West 51st Street
P.O. Box 7447
Tulsa, OK 74105

County Pawnee 132.11
Well Total Depth 4065 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 300

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor H-30 Drilling Inc. License Number 5107

Address 251 North Water, Suite 10, Wichita, KS 67202

Company to plug at: Hour: 11 a.m. Day: 5 Month: 9 Year: 19 87

Plugging proposal received from Dick Davis

(company name) H-30 Drilling Inc. (phone) 316-263-2043

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2001' GL
Anhydrite 961-85'

- 1st plug at Base Anhydrite with 50 sx cement,
- 2nd plug at 30' below base of surface pipe with 40 sx cement,
- 3rd plug at 40' with 10 sx cement,
- 4th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Dan Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 1 p.m. Day: 5 Month: 9 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 980' with 50 sx cement,

- 2nd plug at 330' with 30 sx cement,
- 3rd plug at 40' with 10 sx cement,
- 4th plug to circulate rathole with 15 sx cement,
- 10 sx cement in water well.

9-10-87
RECEIVED
STATE CORPORATION COMMISSION
SEP 10 1987
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.
(If additional description is necessary, use BACK of this form.)

INVOICED (if not) observe this plugging.

DATE SEP 11 1987

Signed Dan Goodrow (TECHNICIAN)

INV. NO. 18078

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date 8-27-87 month day year

API Number 15-145-21,264-0000

OPERATOR: License # 6718 Name Fell Oil & Gas Address 4451 W. 51st Street P.O. Box 7447 City/State/Zip Tulsa, Oklahoma 74105 Contact Person Bruce Taton Phone (918) 446-6114

NW SW SE Sec. 21 Twp. 22 S, Rg. 15 East X West 990 Ft. from South Line of Section 2310 Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5107 Name H-30 Drilling City/State Wichita, Kansas 67202 Well Drilled For: X Oil SWD Infield Mud Rotary Gas Inj X Pool Ext. Air Rotary OWWO Expl Wildcat Cable

Nearest lease or unit boundary line 330 feet County Pawnee Lease Name K.U. Endowment Well # 1 Ground surface elevation 2001 feet MSL Domestic well within 330 feet: yes X no Municipal well within one mile: yes X no Depth to bottom of fresh water 150 Depth to bottom of usable water 250 Surface pipe by Alternate: X 2 Surface pipe planned to be set 350' Conductor pipe required Projected Total Depth 4000" Formation Arbuckle

If OWWO: old well info as follows:

Operator Well Name Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.

Date 8-29-87 Signature of Operator or Agent Bradly G. Swick Title Agent

For KCC Use:

Conductor Pipe Required feet; Minimum Surface Pipe Required 300 feet per Alt. 1 X This Authorization Expires 2-26-88 Approved By 8-26-87

Spud 8-29-87

D.G.

WV YES

300 + of 8 5/8"

C-NW-SW-SE Sec. 21 Twp. 22 S, Rg. 15 East X West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays). If more than 50' into Arbo 50SX

1st plug @ Base Anh. 925' feet depth with 50sx 60/40 por. 6% 2nd plug @ 450' 30' below SP. feet depth with 40sx 40sx 3rd plug @ 40' feet depth with 10sx 4th plug @ feet depth with 5th plug @ feet depth with (2) Rathole with 10sx 15 (b) Mousehole with 10sx

PUSHER Dick Davis TD 4065' FORMATION Arbuckle Top SURFACE PIPE 8 5/8" @ 300 ANHYDRITE 961' ELEVATION 2001.6L 7-5-87 STARTING TIME & DATE 11:00 AM 9-5-87 COMPLETION TIME & DATE 1:00 PM 1st PLUG @ 980 FT. W/ 50 SX 2nd PLUG @ 330 FT. W/ 30 SX 3rd PLUG @ 40 FT. W/ 10 SX 4th PLUG @ FT. W/ SX RAT HOLE CIRCULATED W/ 15' MOUSE HOLE CIRCULATED W/ SX 10 days in water well WATER WELL PLUGGED W/ fill @ 20' CORN SX CEMENT COMPANY Hall Pumped 60/40 6% Dan Technician Swick

RECEIVED STATE CORPORATION COMMISSION

SEP 10 1987

CONSERVATION DIVISION Wichita, Ks