

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-23853-00-00
Spot: ^{SE} NENWSW Sec/Twnshp/Rge: 5-18S-12W
2276 ~~2310~~ feet from S Section Line, 990 feet from W Section Line
Lease Name: EVELEIGH 4100 Well #: 1
County: BARTON Total Vertical Depth: 3367 feet

Operator License No.:	String	Size	Depth (ft)	Pulled (ft)	Comments
<u>101</u>	PROD	5.5	3357		
Op Name: <u>KCC FEE FUND PLUG</u>	SURF	8.625	290		
Address: <u>266 N MAIN ST, STE 220</u> <u>WICHITA, KS 67202</u>					

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/15/2016 11:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: KCC FEE FUND PLUG DBA Phone: (620) 727-3410

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement, 600 # hulls and 10 sx gel.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/15/2016 5:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report: _____ Perfs: _____

Knocked out CIBP. Ran tubing to 3349' and pumped 1000 # gel followed by 40 sx cement w/100 # hulls. Pulled tubing to 1400' and pumped 50 sx cement w/100 # hulls. Pulled tubing to 700' and pumped 25 sx cement w/50 # hulls. Pulled tubing to 350'. Circulated cement to surface with 125 sx cement on casing. Pulled tubing and circulated cement to surface on surface pipe with 40 sx cement. Pressured to 500 psi. Shut in pressure 250 psi.

GPS: 38.51343 -098.67902

KCC WICHITA
JAN 09 2017
RECEIVED

Remarks: QUALITY WELL SERVICE ANGLE FEE FUND PROJECT CONTROL # 20170006-007
Plugged through: TBG

District: 04 Signed Bruce Rodie (TECHNICIAN) CM

JAN 04 2016 KCC WICHITA JAN 09 2017 RECEIVED Form CP-2/3