

1 080260

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER ⁰⁰¹⁷⁹ 15- 145-~~01,000~~ - 0001

NW NE SE , SEC. 28 , T 22 S, R 15 W/X
2310 feet from ~~XXX~~ section line
990 feet from ~~XXX~~ section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6283

Lease Name Tranbarger Well # 1

Operator: The Roxana Corporation

County Pawnee 131.98

Name & Address P. O. Box 1850

Well Total Depth 4061 feet

Great Bend, KS 67530

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 197

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Allen Drilling Company License Number 5418

Address P. O. Box 1389, Great Bend, KS 67530

Company to plug at: Hour: 11:00 am Day: 15 Month: November Year: 19 84

Plugging proposal received from Don Sanders

(company name) Allen (phone) 316-793-5681

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1000' with 50 sx cement

2nd plug at 500' with 40 sx cement

3rd plug at 240' with 40 sx cement

solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 10 sx cement

Plugging Proposal Received by J. H. Metz

(TECHNICIAN)

Plugging Operations attended by Agent?: All Part X None

Operations Completed: Hour: 1:00 pm Day: 15 Month: November Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 1000' with 50 sx cement, 2nd plug at 500' with 40 sx

cement, 3rd plug at 240' with 40 sx cement, 4th & 5th plugs - solid bridge - hulls -

plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with

10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

11-21-84 NOV 21 1984

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Halliburton

(if additional description is necessary, use BACK of this report)

CONSERVATION DIVISION
Wichita, Kansas

INVOICED

(did not) observe this plugging.

DATE 12-4-84

Signed J. H. Metz SQ
(TECHNICIAN)

INV. NO. 5775