

7-10

To: 1 120449
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-145-21,234-0000

NE SE SE, SEC. 25, T 22 S, R 15 W/R

990 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4480

Lease Name Blackwell Well # B-1

Operator: Blackhawk Exploration Inc.

County Pawnee 133.25

Name & Address 200 E. 1st Street, Suite 100

Well Total Depth 4100 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 571

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 11:30 a.m. Day: 10 Month: 7 Year: 19 90

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2943

were: 4 1/2" at 4099' cemented w/100 sx. Perfs at 3877-81 & 3902-04'

1st plug sand back to 3820' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 150 sx cement.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 1 p.m. Day: 10 Month: 7 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded back 4 1/2" casing to 3820' and dumped 4 sx cement on top of sand through bailer, 7-16-90

2nd plug pumped into 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 150 sx cement.

Pumping pressure 0-400 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2800' of 4 1/2" casing.

(if additional description is necessary, use BACK of this form.)

RECEIVED STATE CORPORATION COMMISSION JUL 16 1990

CONSERVATION DIVISION Wichita, Kansas

INVOICED (XXXXXX) observe this plugging.

Signed Duane Rankin (TECHNICIAN)

DATE 7-24-90

INV. NO. 28699