

1 120465

9-11

15-145-20368-0000

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- E-18,538

SW NE SW, SEC. 25, T 22 S, R 15 W

1650 feet from S section line
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3517

Lease Name Barstow Well # 3

Operator: Columbian Resources Corporation

County Pawnee 134.71

Name & Address Box 3501

Well Total Depth 4145 feet

Topeka, KS 66601-3501

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 552

Abandoned Oil Well Gas Well Input Well X SWD Well O&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 9 a.m. Day: 5 Month: 9 Year: 19 90

Plugging proposal received from Mike Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2943

were: 4 1/2" at 4070', Perfs at 3696-3700'

1st plug sand back to 3640' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 125 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 6:30 p.m Day: 11 Month: 9 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded 4 1/2" casing back to 3500' and dumped 4 sx cement on top of sand through bailer,

9-18-90

2nd plug pumped into 8 5/8" surface casing with 350 lb hulls and 8 sx gel, cement circulated on backside of 8 5/8".

3rd plug on 9/11/90 ran 960' of tubing and pumped 40 sx cement,

4th plug pulled tubing to 590' and pumped 50 sx cement,

5th plug pulled tubing to 30' and circulated cement with 10 sx. Used 60/40 Pozmix 6% gel by Allied. Recovered 1817' of 4 1/2" casing

Remarks: (if additional description is necessary, use BACK of this form.)

INVOICED (I did not observe this plugging.)

DATE 9-25-90

Signed [Signature] (TECHNICIAN)

INV. NO. 29416

9-11