

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-145-20243-0000 *R*

Sw 1/4, Sec. *23*, T. *22* S, R. *15* W *X*

_____ feet from N/S section line

_____ feet from W/E section line *R*

TECHNICIAN'S PLUGGING REPORT

Operator License # 8061

Lease Name Smith Twin Well # 1

Operator: Oil Producers Inc
Name & of Kansas

County Rownee

Address Box 39A, Rt #1
Hamiland, KS 67059

Well Total Depth 4130 feet 134.23

Conductor Pipe: Size 8 feet

Surface Casing: Size 8 5/8 feet 225W/100W

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 176, Chase, KS 67524

Company to plug at: Hour: 3:00pm Day: 21 Month: MARCH Year: 1983

VERBAL PLUGGING ORDERS GIVEN TO Bob Brenneman

(company name) Kelso (phone) _____

were: use 50/50 Pozmix, 2% gel - 3% CC - after rec. 1727'
of 4 1/2", pump 3 x hulls, 10 x gel, 70 x cement,
10 x gel, 1 x hulls - release plug - then 70 x cement.
Perfs squeezed to 3068.

Signed R. Barluttan
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 4:15pm Day: 21 Month: March Year: 1983

ACTUAL PLUGGING REPORT Plugged as ordered. Allied
did the cementing. Max. pump pressure
@ 400#, shut in at 400#.

Remarks: 4 1/2" @ 4123' w/ 100 x - RBTD 4017 - Perfs @
3068 to 3992 -

Mr. Steve Durrant observed this plugging.
I hereby certify that the above plugging instructions were given as herein stated
and that I (~~did~~ / did not) observe this plugging.

INVOICED

RECEIVED
STATE CORPORATION COMMISSION

Signed R. Barluttan
(TECHNICIAN)

DATE 4-11-83

MAR 23 1983

INV. NO. 3930-4

CONSERVATION DIVISION
Wichita, Kansas

FORM CP-2/3
Rev. 9-82