

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-193-20392-00-00
Spot: NWNESW Sec/Twnshp/Rge: 34-10S-31W
2310 feet from S Section Line, 3630 feet from E Section Line
Lease Name: HUERTER Well #: 1
County: THOMAS Total Vertical Depth: 4650 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4649		175 SX
SURF	8.625	320		175 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/04/2016 9:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: JOE Company: AMERICAN WARRIOR, INC. DBA Phone: (620) 275-2963

Proposed 8 5/8' surface casing set at 320' w/175 sx cement.
Plugging 4 1/2' production casing set at 4649' w/175 sx cement.
Method: DV Tool set at 2541'.
TD 4650', PBSD 4549'.
Perforations: 4485' - 4488'.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/04/2017 1:30 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Cut hole in 8 5/8" casing. Well equipped with casing hanger. Inserted fitting and pumped 30 sx cement. 8 5/8" surface casing full of cement. Ran tubing to 4480' and pumped 100 sx cement w/300 # hulls. Pulled tubing to 3000' and pumped 100 sx cement w/200 # hulls. Pulled tubing to 1500' and pumped 100 sx cement w/50 # hulls. Cement circulated to surface. Pulled tubing to surface. Connected to 4 1/2" production casing and pumped 20 sx cement.

GPS: 39.13973N -100.77145W

Perfs:

Top	Bot	Thru	Comments
4485	4488		

KCC WICHITA
JAN 24 2017
RECEIVED

---INVOICED---

JAN 24 2017

Remarks: SWIFT SERVICES INC. TICKET # 29,525

Plugged through: TBG

District: 04

Signed Darrel Dipman
(TECHNICIAN)

CM