

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-163-23801-00-00
Spot: NWSENE Sec/Twnshp/Rge: 31-8S-20W
1825 feet from N Section Line, 1150 feet from E Section Line
Lease Name: V L TRUST Well #: 1-31
County: ROOKS Total Vertical Depth: 3770 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3769		175 SX
SURF	8.625	210		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/28/2016 10:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: JOE SMITH Company: SWIFT SERVICES, INC Phone: (620) 275-2963

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement w/500 # hulls and 15 sx gel spacer (100 # bags).
Alt II - 1642' to surface with 175 sx cement.
CIBP at 3695'.
Production perforations: 3678' - 3702'

Plugging Proposal Received By: PAT BEDORE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/28/2016 10:00 AM KCC Agent: PAT BEDORE

Actual Plugging Report:

Hooked to 5 1/2" casing and pumped 50 sx cement w/200 # hulls, then pumped 15 sx gel followed by 170 sx cement w/300 # hulls. Shut in pressure 300 psi. Visually checked 8 5/8" x 5 1/2" annulus and cement was to surface.

GPS: 39.31678N -099.59048W

Perfs:

Top	Bot	Thru	Comments
3700	3702		

KCC WICHITA
JAN 24 2017
RECEIVED

Remarks: SWIFT SERVICES TICKET # 29521

Plugged through: CSG

District: 04

Signed _____

Pat Bedore

(TECHNICIAN)

CM

DEC 29 2016