

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-035-20679-00-00
Spot: NESESWSSE Sec/Twnshp/Rge: 33-34S-4E
466 feet from S Section Line, 1406 feet from E Section Line
Lease Name: BUZZI Well #: 1
County: COWLEY Total Vertical Depth: 3300 feet

Operator License No.: 33405
Op Name: ANSTINE & MUSGROVE INC.
Address: PO BOX 391
PONCA CITY, OK 74602

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3230		
PROD	4.5	3299		150 SX
SURF	8.625	243		220 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/06/2016 8:00 AM
Plug Co. License No.: 31539 Plug Co. Name: SAMS WELL SERVICE, INC.
Proposal Rcvd. from: GARY ANSTINE Company: ANSTINE & MUSGROVE Phone: (620) 441-8165

Proposed Plugging Method: AS PER KCC RULES & REGS / 25 SXS @ 3200, PERF & CIRC 295'-0'.

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 12/06/2016 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TUBING @ 3200', CONSOLIDATED OILWELL SERVICES ESTABLISHED CIRCULATION, MIXED & PUMPED 30 SXS CLASS A COMMON & DISPLACED IN CASING. TAGGED CEMENT @ 2703'. RIH ON WIRELINE, SHOT SQUEEZE HOLES @ 290'-291'. RIH W/ TBG @ 288', CONSOLIDATED OILWELL SERVICES MIXED & PUMPED 135 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 12-6-2016 5:00 PM. CONSOLIDATED CEMENT TICKET # 51938.

Perfs:

Top	Bot	Thru	Comments
3197	3207	CSG	

Remarks: COMPLIANCE / 10 YEAR RULE

Plugged through: TBG

INVOICED
JAN 24 2017

District: 02

Signed

DUANE KRUEGER
(TECHNICIAN)