

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-163-21344-00-01  
Spot: NWSWSESE Sec/Twnshp/Rge: 8-7S-19W  
567 feet from S Section Line, 1060 feet from E Section Line  
Lease Name: DRYDEN Well #: 2 SWD  
County: ROOKS Total Vertical Depth: 3500 feet

Operator License No.: 31569  
Op Name: BACH, JASON DBA BACH OIL PRODUC  
Address: PO BOX 723  
ALMA, NE 68920

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3404		225 SX
SURF	8.625	285		250 SX

Well Type: SWD UIC Docket No: D20359.0 Date/Time to Plug: 01/11/2017 10:30 AM  
Plug Co. License No.: 99974 Plug Co. Name: GLOBAL CEMENTING  
Proposal Rcvd. from: DALE FERLAND Company: BACH, JASON DBA BACH OIL PRO Phone: (785) 302-1435

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/700 # hulls.  
Perforated at 2265' and 910' to surface.  
Perforations at 3405' - 3480'.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 01/11/2017 1:00 PM KCC Agent: PAT BEDORE

**Actual Plugging Report:**

Ran tubing to 3320' and pumped 100 sx cement w/300 # hulls. Pulled tubing to 2100' and pumped 100 sx cement w/200 # hulls to circulate cement to surface. Pulled all tubing. Topped off 4 1/2" casing with 20 sx cement. Hooked to 8 5/8" x 4 1/2' annulus and pumped 50 sx cement. Maximum pressure 150 psi.

GPS: 39.45377 -099.45716

**Perfs:**

Top	Bot	Thru	Comments
3405	3480		

KCC WICHITA  
JAN 24 2017  
RECEIVED

INVOICED  
JAN 24 2017

Remarks: GLOBAL OILFIELD SERVICES TICKET # 2814

Plugged through: TBG

District: 04

Signed

*Pat Bedore*

(TECHNICIAN)

CM

JAN 12 2016

JAN 12 2016